BRUHATH BANGALORE MAHANAGARA PALIKE

Bytarayanapura Division

ckage-1, Includes 2 Works. 1) Providing Basic Amenities and Procurment of Dustbins in Sahakaranagara, Byatarayanapura, anjeevininagar in Ward No. 07, Byatarayanapura. 2) Providing Basic Amenties and procurement of dustbins in Sahakaranagara, yatarayanapura, Sanjeevininagara in Ward No 07, Byatarayanapura.

Job Code :- 007-18-000010, 007-18-000011

Name of Agency :- B.B.UMESH, No 385/1, Near Anjaneya Temple, Bettahalasuru (P), Banglore North- 562157

MODIFIED SCHEDULE - B

Item No	Approved Quantity	Description of Item of Work	Unit	Approved Tender Rates of B.B UMESHA	
				In Figures	In Words
1	15.00	Outdoor PLZ IP Cameras with 20 X optical zoom with controller along with suitable mounting system (PTZ Pan Tilt and Zoom feature is availbale in this camera can be contolled by the software for pan Tilt and zoom feature at the contol center and can be programmed to view at different angles and zoom level continuosly. It operates at day and night and the viewing distance at clarity is about 100 metres	Nos	87,870.00	Rupees Eighty Seven Thousand Eight Hundred Seventy Only
2	90.00	Bracket (Corner Mount / Pole Mount/ Wall Mount) for mounting the PTZ camera.	Nos	4,800.00	Rupees Four Thousand Eight Hundred Only
3	90.00	Outdoor 50 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 50 metres)	Nos	23,700.00	Rupees Twenty Three Thousand Seven Hundred Only
4	90.00	Bracket and weatherproof Installation kit for 50 Meter IP Camera	Nos	1,745.00	Rupees One Thousand Seven Hundred Forty Five Only
5	90.00	Outdoor 30 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 30 metres)	Nos	17,000.00	Rupees Seventeen Thousand Only
6	90.00	Bracket and weatherproof Installation kit for 30 Meter IP Camera	Nos	1,684.00	Rupees One Thousand Six Hundred Eighty Four Only
7	15.00	32 Channel NVR DS 7732 NI- E4 (with 4 Sata Option) the control box and the recording device to connect upto 32 devices, can be cascaded to provide additional cameras	Nos	75,000.00	Rupees Seventy Five Thousand Only
8	15.00	12 TB NAS Box for Back up (NET GEAR) provides storage for the recorded data for quick view back and storage	Nos	2,90,000.00	Rupees Two Lakh Ninety Thousand Only
9	30.00	4 TB SATA for storage and fitted in the NVR Device for storage	Nos	25,820.00	Rupees Twenty Five Thousand Eight Hundred Twenty Only
10	180.00	A suitable sheet metal control panel to house site Equipments (Weather Proof) The power supply and the ethernet connectivity adaptor is stored in this box.	Nos	1,724.00	Rupees One Thousand Seven Hundred Twenty Four Only
11	180.00	Power supply for the camera.	Nos	520.00	Rupees Five Hundred Twenty Only
12	180.00	Ethernet Switch for connectivity to Internet and Camera	Nos	1,073.00	Rupees One Thousand Seventy Three Only
13	135.00	Supply & Laying of Network and Power Cables from Camera to the control Box.	Nos	439.00	Rupees Four Hundred Thirty Nine Only
14	90.00	Video Manager Application Software for Display and Management of Camera on Video Display.	Nos	22,400.00	Rupees Twenty Two Thousand Four Hundred Only
15	90.00	Installation, Erection & commissioning charges	Nos	5,717.00	Rupees Five Thousand Seven Hundred Seventeen Only
16	195.00	Providing Modern Dust Bins	Nos	20,000.00	Rupees Twenty Thousand Only
17	57.92	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 Page No. 5 / Item No. 2.3 of PWD SR 2016-17	Cum	230.00	Rupees Two Hundred Thirty Only
18	22.61	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No.12, Item No. 4.3 of PWD SR 2016-17	Cum	5,939.00	Rupees Five Thousand Nine Hundred Thirty Nine Only

Scanned with CamScanner

Item No	Approved Quantity	Description of Item of Work	Unit	Approved Tender Rates of Rs. In Figures	In Words
19	29.70	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Page No. 23 / Item No. 5.6, PWD SR 2016-17	Cum	5,000.00	Rupees Five Thousand Only
20	13.12	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Page No. 23 / Item No. 5.9, PWD SR 2016-17	Cum	6,000.00	Rupees Six Thousand Only
21	75.96	KSRB 15.1.3 Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications Page No. 113 / Item No. 15.3, PWD SR 2016-17	Sq-m	119.00	Rupees One Hundred Nineteen Only
22	3.55	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications. Page No. 5 / Item No. 2.11 of PWD SR 2016-17	Cum	92.00	Rupees Ninety Two Only
23	257.10	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 Page No. 15 / Item No. 4.28, PWD SR 2016-17	Sq-m	281.00	Rupees Two Hundred Eighty One Only
24	42.76	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1,4.6, No. 13 / Item No. 4.11 / PWD SR 2016-17	Cum	7,250.00	Rupees Seven Thousand Two Hundred Fifty Only
25	4.65	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 Page No. 17 / Item No. 4.46.2 / PWD SR 2016-17	Tonne	73,200.00	Rupees Seventy Thousand Two Hundred Only
26	82.11	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 15 / Item No. 4.18 / PWD SR 2016-17	Sq-m	375.00	Rupees Three Hundred Seventy Five Only
27	209.50	KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 Page No. 25 / Item No. 5.26.2, PWD SR 2016-17	Sq-m	1,107.00	Rupees One Thousand Hundred Seven Only

Scanned with CamScanner

Approved Quantity	Description of Item of Work	Unit	Approved Tender Rates of B.B UMESHA	
			In Figures	In Words
76.49	KSRB 10-3 : Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc., consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with proprietary water proofing compound conforming to IS:2645 over the RCC slab after cleaning the surface before treatment. (b) Laying cement concrete using broken brick bats 25mm to 100mm size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound conforming IS:2645 over 20mm thick layer of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junctions of walls and slabs. (c) After two days of proper curing, applying a second coat of cement lurry admixed with proprietary water proofing compound (d) Finishing the surface with 20mm thick jointless cement mortar of mix 1:4 admixed with proprietary water proofing compound and finally finishing the surface with trowel and neat cement slurry and making of 300x300mm	Sq-m	1,100.00	Rupees One Thousand One Hundred Only
72.52	KSRB15-3-13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114, Item No. 15.21 of PWD SR 2016-17	Sq-m	235.00	Rupees Two Hundred Thirty Five Only
101.00	KSRB15-3.8 : Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114 / Item No. 15.16, PWD SR 2016-17 (Inside Wall)	Sq-m	270.00	Rupees Two Hundred Seventy Only
23.00	KSRB15-7 : Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications. **Page No. 115, Item No. 15.33, PWD SR 2016-17**	Sq-m	30.00	Rupees Thirty Only
261.41	KSRB15-3.9 :Providing, 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114 / Item No. 15.17, PWD SR 2016-17 (Outside Wall)	Sq-m	241.00	Rupees Two Hundred Forty One Only
10.19	Supplying and fixing pressed steel door frames size 125x65 mm manufactured from 1.25mm thick carbon steel or imported steel strips with mitred joints of 900 for door openings and shutters made out of seasoned Honne wood, styles of 30 mm, thick with lock rail of 160 mm, width, top and side rails of 100 mm. width and bottom rails of 250 mm width and panel filling with 12mm thick particle board of exterior grade bonded with phenol formal dehide resin and the shutter shall be rot proof, vermin proof, heat resistant guaranteed against shrinkage, warpage and such other defects for a period of 3 years. This shall be as per approved drawings, specification and direction including cost of conveyance, manufacturing, painting with enamel paint 2 coats over primer coat, cost of labour for all items of work, machinery, equipment and all other incidental charges with all lead, lift, loading and unloading etc., complete. The Hollow portion of the frame to be filled with cement concrete 1:2:4. Page No. 39 / Item No. 7.26, PWD SR 2016-17	Sq-m	4,271.00	Rupees Four Thousand Two Hundred Seventy One Only
5.61	"Supplying and fixing pressed steel window frame of size 100 x 50mm manufactured from 1.25 mm thick carbon steel or imported steel strips with neat mitred joints at 900degree for window openings and shall be suitable to fix M.S. grills as per design and drawings using 12mm dia rods at 100mm Centre to Centre horizontally and two members of M.S flats of 6mmx40mm size at 150mm apart, welded into a frame of 6mmx40mm size M.S. flats with 16mm size lugs, and 8 Nos. of 100mm size hinges, 4 Nos of Butt Stay pins and 4 Nos. Tower bolts and shutters half panelled and hallf glazed with shutters made out of seasoned honne wood, styles of 30mm thick and 100mm width and rails of 30mm thick and 100mm width and using 4mm thick pin headed glass and panel, filling with 12mm thick particle board of exterior grade bonded with phenol formal dehide resin and the shutter shall be rot proof vermin proof, heat resistant guaranteed against shrinkage, warp age and such other defects for a period of 3 years.This shall be as per approved drawing, specification and direction including cost of conveyance, manufacturing painting with 2 coats enamel paint over one coat of primer, cost of labour for all items of work, machinery, equipment and all other	Sq-m	4,637.00	Rupees Four Thousand Six Hundred Thirty Seven Only

Scanned with CamScanner

Item No	Approved Quantity	Description of Item of Work	Unit	Approved Tender Rates of B.B UMESHA	
				In Figures	In Words
35	65.07	KSRB 14.10-1: Flooring with 25mm to 40mm thick polished tandur blue stone slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, , including cost of materials, labour, curing, polishing complete as per specifications. Specification No. KBS Page No. 103 / Item No. 14.15, PWD SR 2016-17	Sq-m	1,350.00	Rupees One Thousand Three Hundred Fifty Only
36	23.00	KSRB 15-14.1 : Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. Page No. 117 / Item No. 15.49.1, PWD SR 2016-17	Sq-m	87.00	Rupees Eighty Seven Only
37	50.00	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer. Page No. 117 / Item No. 15.53.2, SR 2016-17.	Sq-m	102.00	Rupees One Hundred Two Only
38	60.00	KSRB 8.6-7 : Providing and fixing on wall surface 4.0 kg / sq.cm H.D.P.E. rain down water pipes 90 mm outer dia. approved make and brand with necessary specials like shoes, bends and offsets fixed with iron clamps, wall plugs, screws, including cost of materials, labour, complete as per specifications. Page No. 47 / Item No. 8.18, PWD SR 2016-17	Mtr	522.00	Rupees Five Hundred Twenty Two Only
		Extra Items			
E1	5.00	Providing and Fixing Leaf Cutter Machine including transportation	Nos	2,49,000.00	Rupees Two Lakh Thirty Thousand Only

Signature of Contractor

Executive Engineer
Byataravanapura Division
B.B.M.P , Banglore-92

ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ, ಬೆಂಗಳೂರು

Scanned with CamScanner